

Highly-Modified, Low Air Void Projects in Utah and Montana

Dave Johnson, P.E.

Senior Regional Engineer

Asphalt Institute



Hey Howard, Tell us What You Think...



Howard Anderson, PE
State Asphalt Engineer
Utah DOT Materials Division

Past Experience With Highly Modified and/or Thick Lifts



- South Carolina
 - Single-lift at 7.9 inched
 - Consistent densities ~95%
- NCAT
 - South Carolina & Kraton sponsored
 - Unmodified & Highly Modified
 - Great densities top to bottom
 - Great performance
 - 5.75-inch Kraton section gave perpetual performance
- Utah
 - Past laboratory work
 - Hamburg driven
 - Typical 12.5 mm mix
 - Multiple samples up to 6.8% binder
 - 40,000 passes
 - No Hamburg failures (<10 mm)
 - Two secondary highways
 - Simply substituted binder into the mix design
 - Constructed in 2017
 - Typical lift thicknesses
 - Excellent performance

Table 10

PG76-34 Highly Modified	
<u>Original Binder</u>	
Dynamic Shear Rheometer, AASHTO T 315 @ 76° C, G*, kPa	
@ 76° C, phase angle, degrees	1.30 Min.
Rotational Viscometer, AASHTO T 316 @ 135° C, Pa.s	70.0 Max.
Flash Point, AASHTO T 48 °C	3 Max.
	260 Min.
<u>RTFO Residue, AASHTO T 240</u>	
Dynamic Shear Rheometer, AASHTO T 315 @ 76° C, G*/sinδ, kPa	
Elastic Recovery, AASHTO T 301 mod (a) %	2.20 Min.
	90 Min.
<u>PAV Residue, 20 hours, 2.10 MPa, 100 °C, AASHTO R 28</u>	
Dynamic Shear Rheometer, AASHTO T 315 @ 25° C, kPa	
Bending Beam Rheometer, AASHTO T 313 @ -24° C, S, MPa	
	5,000 Max.
	300 Max. 150 Min.
@ -24° C, m-value	0.300 Min.
Delta Tc from additional BBR test, ASTM D7643 @ -30° C	-1.0 Min.
(a) Modify paragraph 4.5 as follows: Stop the ductilometer after 20 cm has been reached and within 2 seconds. Sever the specimen at its center with a pair of scissors.	

+/- 5% SBS

Wendover Pilot Project Overview



- Location Information

- Port of Entry on I-80 Near Wendover, UT
- High Truck Volume (51%), AADT 7,900
- 2-2.5 Million ESALs/year
- Very Hot in the Summer
- LTPPBind = PG64-28 (98% reliability)

- Project Scope

- Mill and Inlay 6.0 Inches of PCC
- ~330 Ton Project
- Highly Modified Binder
- Dense-Graded Mixture
- Construct in a Single Lift
- ~2-Hour One-Way Haul

Project Location




Google Maps

Property	Mix Design Requirement	Mix Design Value
Asphalt Binder	PG 76-34	PG 76-34
Gyrations	50	50
NMAS Crushed Aggregates	12.5 mm 100%	12.5 mm 100%
Asphalt Content	6.0 % minimum	6.0% (5.33% Virgin, 0.67% RAP Binder)
Air Voids	1.0	1.0% (0.1% at 75 gyrations)
Voids in Mineral Aggregate	15.0-17.0	15.3
Voids Filled with Asphalt	90.0-95-0%	93.3%
Drain Down	0.3% max	0.0%
RAP	15% max	15%
Hamburg Depth (note bath temperature increased from 50 to 54°C for second 20,000 passes) Slab Void target 4 %	7.0 mm max after 20,000 passes	3.9 mm
	10.0 mm max after 40,000 passes	6.1 mm


Hamburg Graphs

PMW WheelTracking Test




First 20,000 Passes

PMW WheelTracking Test



Second 20,000 Passes – same specimen

Hi-Mod binders minimize rutting



Test Strip Construction

- At Staker-Parson's Beck Street Facility
- Aggregate base vs. Portland cement concrete
- Virtually no haul vs. 2+ hours



Test Strip Construction



Staker Plant Test Strip

June 2, 2021



Test Strip Construction



Test Strip Lessons Learned



- Density of 97% or more was easily achieved
- Regular rolling equipment and procedures followed
- Feeding while placing such a large volume of mix was achieved, but had challenges
- Mix was stable even with roller overhang
- No significant issues encountered

Wendover Construction




Western Section Coming Off I-80



Eastern Section Off the Scale



Paving Operations




Paving Operations



Paving Operations



Time vs. Temperature



Density Results



Core	Total Thickness	Top Half Density	Bottom Half Density
1	6.27 inches	97.9%	98.0%
2	6.27 inches	97.8%	94.4%
3	6.1 Inches	97.2%	92.8%
4	6.1 Inches	97.3%	97.6%

Lessons Learned – Early Post Traffic Performance

- Highly modified asphalt can be successfully constructed even with a 2+ hour haul
- High densities were easily achieved
- Exceptional performance
 - Approximately **6 million** commercial trucks over 4+ years
 - **No discernable movement**
 - **No cracking**
 - **ZERO distress**



Highly Modified, High Density, Low Air Void Installations in Utah 2021-2023

Project Description	Pavement Description	Design Thickness	Construction Year	HiMod Tonnage	Observed Density
Wendover	Port of Entry off I-80	6 Inches	2021	330	+97%
I-15 near Parish Lane	Overlay of PCC both NB and SB	3 Inches	2022 and 2023	2,216 NB 1,258 SB	+96.5%
SR-196; MP 24 to 80 F-0196(7)24	13-mile Overlay	1.5 Inches	2023	15,506	+96%
SR 173; 4800 W. to Bangerter Highway F-0173(42)4	Overlay	1.5 Inches	2023	5,001	+96%
I-80, I-15, I-215 Bridge Decks	7 Bridge Decks, Contractor Change Ordered	3-4 Inches	2023	unknown	+96%

- 3-inch lift directly over very poor PCCP that had only crack sealing done prior to the overlay.
- Same mix, same contractor as Wendover
 - Average thickness = 2.97 inches
 - Average binder content = 5.94%,
 - Average VMA = 15.7
 - Average density of = 97.3%
- Planned overlay installed in SMA 2024 – no distresses were present
- Excellent performance at the 3-year mark

2024 Bid Lettings – Dominate Asphalt Mixture in Utah



Project Description	Pavement Description	Design Thickness	Construction Year	HiMod Tonnage	Has Thick Lift?
US 6 Interchange F-0006(230)174	High Traffic Interchange	5 inches	2024	4,123	Yes, 5 inch
I-80 MP 41 to 50 F-I80-2(82)41	9-mile Overlay	1.5 inches	2024	38,932	No
I-215 Ramps; State, Fashion F-R299(458)	Overlay of Concrete	3 inches	2024	1,673	No
US 40 East of Duchesne	10-mile Overlay	2 inches	2024	18,000 (estimate)	No
US 6 Tucker to Soldier Summit F-0006(245)204	7-mile mill and Overlay truck lane Overlay entire road	4 inches – truck lane Plus 2-inch to Truck lane and rest of road	2024	52,666	Yes, 4 inch
I-80: Near Airport Entrance Bridge Preservation F-R299(270)	Overlay of 19 bridge decks	3 inches	2024	4,603	No
SR-276 and SR-95 F-R499(457)	45 -Mile Overlay	2 Inches	2024	84,764	No
SR-261 and SR-276 Near Bluff	Overlay	2 inches	2024-2025	204,728	Yes, 7 inch
US-191: Dry Valley to Hatch Wash F-0191(206)89	Overlay	2 inches	2024	16,969	No
SR-171; 700 W. to State Street F-0171(72)9	Overlay	1.5 inches	2024	4,752	No
SR-190; Pavement Preservation F-0190(29)2	Overlay	1.5 inches	2024	11,105	No
US-89: Passing Lanes near Buckskin Wash S-0089(572)35	Overlay	2 inches	2024	17,906	Yes, 5 inch
US-89, SR-204 to SR-134	SMA changing to HiMod	2 inches	2024	11,500	No
SR 35 F-0035(13)0	Overlay	1.5 inch	2024	14,000 (estimate)	No
I-215 Reconstruction	Rubblize PCC Pavement and Overlay	5.5 inches	2025	In design	Yes, 4 inch
			Total:	+500,000	

- Originally – remove and replace with PCC
- Evaluated an option with asphalt
 - Rubblize existing PCC
 - Overlay with Highly-Modified, Low Air Void Mixture (5.5 inches)
 - 1.5-inch leveling course
 - 4-inch overlay
 - **\$40 Million Dollar Savings over PCC option!**
- **Using the savings to extend project 17 miles for ramp reconstructions**
- Recently awarded to Granite Construction (\$111M)


AI Beam Fatigue Testing



Mixture	Specimen	Air Voids (%)	Strain ($\mu\epsilon$)	Flexural Modulus at 50 cycles, MPa	Cycles to Failure (N_f) Cycles*Modulus (AASHTO T321)
				Test Data	Test Data
PG 64-34 - Typical Mix	1	7.7	300	7,491	1,199,504
	2	7.1	400	7,879	162,013
	3	6.9	475	7,542	171,958
	4	6.8	525	7,482	23,894
	5	7.4	600	7,360	12,162
PG 76-34 - HiMod Mix	1	4.2	475	6,104	7,817,272
	2	3.8	525	6,320	1,200,843
	3	3.9	600	5,882	913,716
	4	4.0	675	5,655	276,589
	5	4.3	750	5,030	20,180

- Density of 96+% is common
- Regular rolling equipment and procedures followed
- Feeding while placing of a large volume of mix was achieved
 - Requires careful planning
- Mix is stable and workable
- Thin lift (1.5”) projects are becoming common
- Bridge decks
- No distresses to date nor problematic installations
 - Longitudinal joints (94%) on thinner lifts sometimes a challenge
- DOT and Utah Contractors love this mix


Utah Mixture Trends




Utah Mixture Trends (Highway Only)



Average \$/ton



Project Mat Densities



Other Projects in the Rockies



- Montana Department of Transportation
 - 19th Street in Bozeman
 - Emulated the Utah specification
 - MSCR PG 64E-34
 - 9.5 mm
 - Project awarded 75%
 - < Engineer's Estimate
 - 2025 construction
- More in a moment
- Idaho Transportation Department
 - Initial project identified
 - Emulating the Utah Specification
 - 2026 construction target
- Colorado Department of Transportation
 - Scoping for candidate project
 - Emulating the Utah Specification
 - 2026 construction target

Thanks to our Members !



Mark Blow
mblow@asphaltinstitute.org
605-351-8649



Contact Info

Thank You - Questions ?